Preliminary Land Use Service (PLUS)

Delaware State Planning Coordination


122 William Penn Street • Dover, DE 19901 • Phone: 302-739-3090 • Fax: 302-739-5661


Purpose of PLUS --The PLUS process is intended to provide consolidated State comments regarding the proposed project. The Applicant is encouraged to submit the application during the concept stages of planning as this proces

Pleasor no vill er applic (302) PLUS Inves 1. Pr 2. Lc 5. If	ng with the local jurisdiction but before complete this PLUS application in its translatable please evaluar. Means			
2. Lo 3. Pi 5. If 6. O	nable the state staff to review the project ant and/or developer at the time of revience 739-3090.	entities. All questions must be answered wered questions on this form could lead to of the form the scheduled meeting and to have aw. If you need assistance or clarification, 2014-05-01	delays in scheduling your review. This form e beneficial information available for the please call the State Planning Office at	
3. Pa 5. If 6. O	roject Title/Name: Lands of Star	nian 7 LLC		
5. If B. O	ocation (please be specific): 360' +/	- Southwest of the Int. of Hon	neysuckle Drive & Route 7	
B. O	arcel Identification #: 08-050.00-0	013 4. County or Local located: Ne	al Jurisdiction Name: where project is	
A	contiguous to a municipality, are you se	peking annexation: N/A		
	wner's Name: Stanlan 7 LLC			
	ddress: 234 North James St.	,		
u	ity: Newport	State: DE	Zip: 19804	
Pl	hone: 302-999-0708	Fax:	Email: afinerosky@pettinaro.co	
7. E	Equitable Owner/Developer (This Person is required to attend the PLUS meeting):			
A	ddress: N/A		F	
C	ity:	State:	Zlp:	
Pi	hone:	Fax:	Email:	
8. Pr	Project Designer/Engineer: Carmine Casper / Howard L. Robertson, Inc.			
Ac	ddress: 801 Brandywine Blvd.	ř.		
CI	ity: Wilmington	State: DE	Zip: 19809	
Pl	hons: 302-764-2456	Fex: 302-764-7022	Email: hirobertsoninc@comcast.ne-	
9. PI				

Information Regarding Site:				
O. Type of Review: Rezoning, if not in compliance with certified comprehensive plan Site Plan Review Subdivision				
11. Brief Explanation of Project being reviewed: Proposed 17,833 sq. ft. retail				
If this property has been the subject of a previous LUPA or PLUS review, please provide the name(s) and date(s) of those applications.				
12. Area of Project (Acres +/-): 22.23 Number of Residential U				
13. Present Zonlog: S	14. Proposed Zoning: CN			
15. Present Use:	16. Proposed Use: 17,833 sq. ft. retail			
17. Water: Central (Community system) Individual On-Site Public (Utility) Service Provider Name: Artesian Water Company				
Will a new public well be located on the sile? ☐ Yes 🔳 No				
18. Wastewater:	- 1-100			
Will a new community wastewater system be located on this site				
 If residential, describe style and market segment you plan to target (Example- Age restricted): N/A 				
20. Environmental impacts: Drainage Discharge				
How many forested acres are presently on-site? How many forested acres will be removed?				
4.5 ac. To your knowledge, are there any wetlands, as defined by the U.S. Army Corps of Engineers or the Department of Natural Resources and Environmental Control, on the site?				
Are the wetlands: Tidal Acres: Non-fidal Acres:				
If "Yes", have the wettands been defineated? 🔳 Yes 🔲 No				
Has the Army Corps of Engineers signed off on the delineation? \Box	fes 🗐 No			
Will the wellands be directly Impacted and/or do you anticipate the ne describe the impacts:	ed for wetland permits? 🔲 Yes 🔳 No If "Yes",			
How close do you anticipate ground disturbance to wetlands, streams	, wells, or waterbodies? Over 100 feet			
21. Does this activity encroach on or impact any tax ditch, public ditc	n, or private ditch (ditch that directs water off-site)? Yes No			
22. List the proposed method(s) of stormwater management for the	site: Bio-Retention			
23. Is open space proposed? Yes \(\sum No If "Yes," how much	1 [?] 19.8 Acres:			
What is the intended use of the open space (for example, active recre- wildlife habitat, historical or archeological protection)? Stormwater	ation, passive recreation, stormwater management, Management			
24. Are you considering dedicating any land for community use (e.g.	, pailce, fire, school)? 🔲 Yes 🏾 📕 No			

25. Please estimate How many vehicle trips will this project generate on an average weekday? A trip is a vehicle entering or exiting, If traffic is seemonal, assume peak season: 801 TRIPS
What percentage of those trips will be trucks, excluding vans and pick-up trucks? 2 %
26. Will the project connect to state maintained roads? We Yes No
 Please list any locations where this project physically could be connected to existing or future development on adjacent lands and indicate your willingness to discuss making these connections. Currently connected to adjacent land, no others proposed.
28. Are there existing sidewalks? (If Yes No; blke paths (III Yes No Are there proposed sidewalks? (I Yes (III No; blke paths (I Yes IIII)
to there an opportunity to connect to a larger bilize, pedestrian, or transit network? Yes No
29. To your knowledge, is this site in the vicinity of any known historic/cultural resources or sites? Yes
Has this site been evaluated for historic and/or cultural resources? Yes No
Would you be open to a site evaluation by the State Historic Preservation Office?
30. To promote an accurate review of your parcel's feetures, would you permit a State agency site visit? Yes \(\subseteq \text{No}\) Person to contact to arrange visit:
31. Are any federal permits, licensing, or funding auticipated?
I hereby certify that the information on this application is complete, true and correct, to the best of my knowledge. March Grant Grant
Signature of Person completing form Date (If different than property owner) Stoned application must be received before application is scheduled for PLUS review.
This form should be returned to the Office of State Planning electronically at Dorothy.morris@state.de.us along
with an electronic copy of any site plans and development plans for this site. Site Plans, drawings, and location maps should be submitted as image files (JPEG, GIF, TIF, etc.) or as PDF files. GIS data sets and CAD drawings
may also be submitted. [Celectronic Copy of Beaplan's not available contact Dorothy at (302) (39-3090 for notine)
instructions: A signed copy should be forwarded to the Office of State Planning, 122 William Penn Street, Dover, DE
19901. Thank you for this input. Your request will be researched thoroughly. Please be sure to note the contact person so we may schedule your request in a timely manner.







Eileen P. Fogarty General Manager

Department of Land Use

April 7, 2014

Mr. Carmine Casper Howard L. Robertson, Inc. 801 Brandywine Blvd. Wilmington, DE 19809

RE: Stanlan 7 LLC - Application No. 2014-0092-S

The Department of Land Use is in receipt of the above submission and finds that it is complete. Pursuant to Section 40.31.113C.1. you must now submit the major plan and/or rezoning to the Office of State Planning for Preliminary Land Use Service (PLUS) review.

Upon receipt of the PLUS report and a finding by the Department that the exploratory plan is in general compliance with Chapter 40 of the County Code, the exploratory plan shall be scheduled for the next available Planning Board public hearing.

If the application is also a rezoning, the Department upon receipt of the PLUS report must first prepare a rezoning ordinance to be introduced at County Council. Following the introduction, the application will then be scheduled for the next available Planning Board public hearing.

Sincerely

Antoni Sekowski

Planner III

c.c. Stanlan 7 LLC

Dorothy Morris - Office of State Planning

Phone: 302-395-5400 Fax: 302-395-5587

Department of Land Use Exploratory Report

Date: April 9, 2014

Engineering firm: Howard L. Robertson, Inc. – Carmine Casper

Application number: 2014-0092-S

Name of project: Lands of Stanlan 7 LLC

Description: 17,883 s.f. shopping center on 22.23 acres
Type of plan: Minor Rezoning Land Development plan

Project Review Team -

Planner Antoni Sekowski at 395-5414 or <u>asekowski@nccde.org</u>
Engineer John Gysling, P.E. at 395-5414 or <u>jgysling@nccde.org</u>

Historic Valerie Cartolano at 395-5440 or <u>vcartolano@nccdV</u>
Transportation Owen Robatino at 395-5427 or <u>orobatino@nccde.or.</u>

Special Services Robert Magnotti at 395-5722 or magnotti@nccde.org

Anto ni Seko

Digitally signed by Antoni Sekowski DN: cn=Antoni Sekowski, o=New Castle County Government, ou=Department of Land Use, email=asekowski @nccde.org, c=US Date: 2014.04.09 15:49:15 -04'00'

Status of Review:-

Acceptable for General Compliance for Office of State Planning PLUS Review and Planning Board public hearing. Upon receipt of the Office of State Planning PLUS written report, the exploratory plan will be scheduled for a Planning Board public hearing on the next available hearing date. The Department will issue an additional review report subsequent to the Planning Board public hearing which will either find the plan acceptable to proceed to County Council after addressing all comments and/or studies or, the Department will find the plan unacceptable wherein a revised exploratory plan submission must be made to address all comments and/or studies.

Public Hearings:

PLUS Planning Board County Council

Planning

- 1.) The proposed rezoning from S to CN may be considered inappropriate at this time. At the joint Department and Planning Board public hearing, the applicant should be prepared to discuss the plan's conformance with the Comprehensive Development Plan, impact upon the surrounding area and infrastructure, compatibility of land use intensity and scale of development, character of the neighborhood, zoning and use of nearby properties and the suitability of the property for the proposed use. Rezoning applications follow the procedure in Section 40.31.113 of the County Code.
- 2.) In meetings with the Department, building elevations were presented and revisions discussed. Submit copies of the agreed to conceptual designs which should be made part of the rezoning consideration as well. At the previous meeting, minor site design

- revisions were also discussed. Confirm those have been addressed on the current submitted plans.
- 3.) Provide a more detailed analysis in the wetland report, per Chapter 40, Article 33, General Definitions, Wetlands Report. Specifically, include data forms and narrative that will clarify why the NWI maps do not depict the actual wetlands onsite, especially in the area where the National line overlaps the line defining the buildable area. Plan notes should clearly define the area of the wetlands investigation;
- 4.) Line L 1-29 appears to stipulate that resources exist downslope of it. Plan notes should clearly reflect that all areas within the proposed conservation easement are considered 100% protected. The property owner reserves the right to further define resources within the protected area in the future. The 50 foot buffer line should then be properly labeled and regulated as an RBA. Note that the Limits of Disturbance (LOD) cannot be located within the RBA. Demonstrate that any proposed disturbance is permitted in accordance with Table 40.10.210 of the NCCC;
- 5.) Delineate full 12'X60' loading bays in accordance with Section 40.22.621 of NCCC. Provide landscape islands for parking spaces which adjoin the loading bays;
- 6.) The Prohibitive and Precautionary Slopes appear to be more extensive than what is currently delineated on the plan. Note that Chapter 40, Article 33, General Definitions outline that any area where such slopes exists in any continuous horizontal increment of 50 feet or more shall be considered steep slopes. Note that the Prohibitive Slopes are 100% protected. Revise the plan to remove the LOD from the Prohibitive Slopes. Additionally, provide a narrative to demonstrate compliance with 40.10.340.B of the NCCC for disturbance of Precautionary Slopes;
- 7.) Submit a Landscape/lighting plan for review and approval. (Table 40.04.111, Article 23, Division 40.22.700);
- 8.) The center landscape island must be curbed;
- 9.) Remove bufferyard notes from Sheet 1 of the plan, per Appendix 1.2, Chapter 40 of the NCCC:
- 10.) Remove notes 11 and 15 from Sheet 1 of the plan, per Appendix 1.2, Chapter 40 of the NCCC;
- Provide legible road names and a north arrow in the location map, per Plan Requirement No. 3, Appendix 1, Chapter 40 of the NCCC;
- 12.) Connect the sidewalk to the existing bike path and extend it as may be directed by Deldot.
- 13.) Show all trash disposal areas and note they must be screened on all sides. (Sec. 40.03.431)

- 14.) Add the application number to the plan and reference it on all correspondence. (Appendix 1- 2.A.2.d.);
- 15.) Reference existing access agreements on the plan. It appears that the existing access agreement with the adjoining parcel may need to be updated. Please contact this office to discuss further;
- 16.) Submit a complete LDIA information sheet to initiate the performance surety process. (Sec. 40.31.820)
- 17.) If a complete record plan submission is not made within thirty-six months of the date of the Department's initial review, the application will be expired in accordance with Section 40.31.390 of the County Code. (Sec. 40.31.390)

Engineering

The Engineering Section within the Department of Land Use has reviewed the site plan submission for the referenced project and finds the plan conditionally acceptable subject to the following comments. Plan was received on March 28, 2014 and comments issued on April 7, 2014. (6 days)

- 1. Project application meeting was held on April 4, 2014. The project was reviewed and the steps necessary to demonstrate compliance by offset option was concluded. Results of the meeting will be sent electronically to all parties.
- 2. Provide a Grading Plan, Sediment and Stormwater Plan, checklists and fees pursuant to NCCDC 12.03.006 and 12.04.006 for construction plan submission.
- 3. Disturbed acreage does not agree between SLD-1 form and plan.
- 4. Conclusion within the stormwater narrative that infiltration is not feasible with rates of 0.5 inches per hour is not supported by data.
- 5. Project site may have been filled in the past. Provide any available information that may reveal the extent and nature of the fill. The fill may be the reason for the precautionary slopes. Care shall be exercised in the design of the embankment for any proposed stormwater facility.
- 6. Provide an outfall location for the proposed stormwater facility supported by topography and or photos that locate a channel or other location that will provide a stable and non-erosive point of discharge.

Comments to be addressed at construction stage:

- 7. Provide results of infiltration testing to determine feasibility of practices that rely on infiltration.
- 8. Please contact the Department of Special Services to determine the fee amount to include in the following note in accordance with UDC 40.27.240. Place the following note on the Record Plan.

Long Term Non- Residential Stormwater Management Fee:

"The Owner/Developer shall pay, to New Castle County, funds for non-residential storm water management facility maintenance pursuant to Section 40.27.240 of the County Code. The funds shall be used for the costs associated with facility maintenance and inspections. An amount of \$ XXXXXX shall be funded prior to the completion and use of any of the improvements proposed by this plan. The Department of Land Use shall withhold the approval of the stormwater as-built submission until the Department of Land Use is furnished with satisfactory written proof that the funds have been paid to New Castle County in accordance with the requirements."

The Engineering Section makes every reasonable effort to identify all code deficiencies with each review. Any non-compliant item discovered throughout any stage of the process is still valid and must be resolved prior to recordation.

Please identify and locate the revisions to the plan sets made as a result of these comments in order to facilitate an efficient review of the next submission of this application. Include an electronic copy of your next and all subsequent submissions. Also, to help us better serve you, please provide advance notice on your resubmission date so that we can be available to meet if necessary.

Mapping

Property addresses not assigned at this time.

Transportation

Based on submitted traffic information and staff evaluation, the Transportation Section has determined the subject plan requires a Traffic Impact Study (TIS). This requirement is in accordance with Section 40.11.120 of the New Castle County Code.

The TIS shall be prepared according to Article 11 of the County Code and Chapter 2 of DelDOT's Standards and Regulations for Subdivision Streets and State Highway Access. The Applicant shall contact DelDOT to schedule a scoping meeting, per Sections 40.11.122 and 40.31.113 of the Code. A copy of the completed TIS shall be submitted to the Transportation Section. Please notify the appropriate parties of this requirement.

Standard Approvals and Comments before Recordation

DelDOT (Sec. 40.31.114.C.1.) Fire Marshal (Sec. 40.31.114.C.2.)


LDIA (Sec. 40.31.820)

Landscape/Lighting plan (Appendix 1-1.C.1.b., Art. 23 and Table 40.04.111.)

Water Capacity Certification (Form 40.05.310)

DelDOT Office of Aeronautics

c.c. Stanlan 7, LLC






Mapping provided by the Delaware Office of State Planning Coordination www.stateplanning.delaware.gov

Location Map







PLUS Project Areas

2007 Land Use

Single Family Dwellings

Multi-Family Dwellings

Industrial Commercial

雅涵 Transportation/Communication/Utilities Mixed Urban/Built-up

Institutional/Governmental

Recreational

Deciduous Forest Mixed Forest

Shrub/Brush Rangeland

Man-made Reservoirs and Impoundments

Open Water Emergent Wetlands - Tidal and Non-tidal


Sandy Areas and Shoreline

Location Map





Mapping provided by the Delaware Office of State Planning Coordination www.stateplanning.delaware.gov



PLUS Project Areas

Legend

Stanlan 7 2014-05-01





Mapping provided by the Delaware Office of State Planning Coordination www.stateplanning.delaware.gov